

Addendum No. 2

- Please read the following statement in its completeness.
- Please Note this does not change any of the previously set dates for Questions, Pre Meetings, Submission Deadlines, etc.

The following changes have been made regarding the specifications for the individual units being requested in this RFP.

- *Section C: Floor Construction*
 - Ramp is specified to be smooth stainless steel. JCPS instead is requiring the ramp to be diamond tread plate. JCPS will not accept a submission that includes the previously stated smooth steel.
- *Section O: Refrigeration Equipment*
 - Condensing units need to be factory insulated or it becomes the responsibility of the vendor to ensure they are insulated before completion date
- *Section F: #12*
 - JCPS is removing the specification regarding the door switch
- *Section P: #5*
 - Updating of language to now read as follows: Suction and liquid line must be wrapped with Armaflex insulation to 3" of the condensing unit and include PVC wrap over the Armaflex as an added layer of protection.